

BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2015-16/RD/WORK_INDENT18391/CALL-2

APPROVED SCHEDULE - B

EE/RTP/BBMP/E-PMT/03/2015-16, Date: 22.01.2016

Construction of RCC Drain at 6th Cross in Patel Pillegowda Layout in ward no 10 (Doddabommasandra), Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N M SHIVAKUMAR		
				In Figures		In Words
1	220	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	83.0	18260.00	Rupees Eighty Three Only
2	33	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4300.0	141900.00	Rupees Four Thousand Three Hundred Only
3	69.3	Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work	Cum	5900.0	408870.00	Rupees Five Thousand Nine Hundred Only
4	4.16	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 TMT Bars FE 500 etc complete as per specifications and directions of engineer in charge of the work	Tonne	69911.0	290829.76	Rupees Sixty Nine Thousand Nine Hundred Eleven Only
5	528	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	307.0	162096.00	Rupees Three Hundred Seven Only
6	7.92	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	5490.0	43480.80	Rupees Five Thousand Four Hundred Ninety Only


Executive Engineer
 Byatarayanapura Division
 Yelahanka Zone, B.B.M.P.
 Bangalore - 560 092

23/5/16

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of N M SHIVAKUMAR		
				In Figures		In Words
7	198	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete 7.5 cms thick etc complete as per specifications and directions of engineer in charge of the work	Sqm	663.0	131274.00	Rupees Six Hundred Sixty Three Only
8	1100	Providing chamfering edges to stone slab 2.5cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	36.0	39600.00	Rupees Thirty Six Only
9	198	Providing two line dressing to granite stone slab / granite stone masonry as per specifications. etc complete as per specifications and directions of engineer in charge of the work	Sqm	924.0	182952.00	Rupees Nine Hundred Twenty Four Only
10	220	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means including loading and unloading. From 0.00 to 11.90 Km etc complete as per specifications and directions of engineer in charge of the work	Cum	106.0	23320.00	Rupees One Hundred Six Only
Total					1442582.56	

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

23/03

23/3/16